



HT Series

Digital Video Recorder

Manual (Rev.5)





WARNING

**RISK OF ELECTRIC SHOCK
DO NOT OPEN**



**WARNING: TO REDUCE THE RISK OF ELECTRIC SHOCK,
DO NOT REMOVE COVER (OR BACK).
NO USER-SERVICEABLE PARTS INSIDE.**



The lightning flash with arrowhead symbol, within an equilateral triangle, is intended to alert the user to the presence of uninsulated “dangerous voltage” within the product’s enclosure that may be of sufficient magnitude to constitute a risk of electric shock.



The exclamation point within an equilateral triangle is intended to alert the user to the presence of important operating and Maintenance (servicing) instructions in the literature accompanying the appliance.

COMPLIANCE NOTICE OF FCC:

THIS EQUIPMENT HAS BEEN TESTED AND FOUND TO COMPLY WITH THE LIMITS FOR A CLASS A DIGITAL DEVICE, PURSUANT TO PART 15 OF THE FCC RULES. THESE LIMITS ARE DESIGNED TO PROVIDE REASONABLE PROTECTION AGAINST HARMFUL INTERFERENCE WHEN THE EQUIPMENT IS OPERATED IN A COMMERCIAL ENVIRONMENT. THIS EQUIPMENT GENERATES, USES, AND CAN RADIATE RADIO FREQUENCY ENERGY AND IF NOT INSTALLED AND USED IN ACCORDANCE WITH THE INSTRUCTION MANUAL, MAY CAUSE HARMFUL INTERFERENCE TO RADIO COMMUNICATIONS. OPERATION OF THIS EQUIPMENT IN A RESIDENTIAL AREA IS LIKELY TO CAUSE HARMFUL INTERFERENCE, IN WHICH CASE USERS WILL BE REQUIRED TO CORRECT THE INTERFERENCE AT THEIR OWN EXPENSE.

CAUTION: CHANGES OR MODIFICATIONS NOT EXPRESSLY APPROVED BY THE PARTY RESPONSIBLE FOR COMPLIANCE COULD VOID THE USER’S AUTHORITY TO OPERATE THE EQUIPMENT. THIS CLASS OF DIGITAL APPARATUS MEETS ALL REQUIREMENTS OF THE CANADIAN INTERFERENCE-CAUSING EQUIPMENT REGULATIONS.

The information in this manual is believed to be accurate as of the date of publication. The information contained herein is subject to change without notice. Revisions or new editions to this publication may be issued to incorporate such changes.

IMPORTANT SAFEGUARDS

1. Read Instructions

All the safety and operating instructions should be read before the appliance is operated.

2. Retain Instructions

The safety and operating instructions should be retained for future reference.

3. Cleaning

Unplug this equipment from the wall outlet before cleaning it. Do not use liquid aerosol cleaners. Use a damp soft cloth for cleaning.

4. Attachments

Never add any attachments and/or equipment without the approval of the manufacturer as such additions may result in the risk of fire, electric shock or other personal injury.

5. Water and/or Moisture

Do not use this equipment near water or in contact with water.

6. Accessories

Do not place this equipment on an unstable cart, stand or table. The equipment may fall, causing serious injury to a child or adult, and serious damage to the equipment. Wall or shelf mounting should follow the manufacturer's instructions, and should use a mounting kit approved by the manufacturer.

7. Power Sources

This equipment should be operated only from the type of power source indicated on the marking label. If you are not sure of the type of power, please consult your equipment dealer or local power company.

8. Power Cords

Operator or installer must remove power and TNT connections before handling the equipment.

9. Lightning

For added protection for this equipment during a lightning storm, or when it is left unattended and unused for long periods of time, unplug it from the wall outlet and disconnect the antenna or cable system. This will prevent damage to the equipment due to lightning and power-line surges.

10. Overloading

Do not overload wall outlets and extension cords as this can result in the risk of fire or electric shock.

11. Objects and Liquids

Never push objects of any kind through openings of this equipment as they may touch dangerous voltage points or short out parts that could result in a fire or electric shock. Never spill liquid of any kind on the equipment.

12. Servicing

Do not attempt to service this equipment yourself. Refer all servicing to qualified service personnel.

13. Damage requiring Service

Unplug this equipment from the wall outlet and refer servicing to qualified service personnel under the following conditions:

- A. When the power-supply cord or the plug has been damaged.
- B. If liquid is spilled, or objects have fallen into the equipment.
- C. If the equipment has been exposed to rain or water.
- D. If the equipment does not operate normally by following the operating instructions, adjust only those controls that are covered by the operating instructions as an improper adjustment of other controls may result in damage and will often require extensive work by a qualified technician to restore the equipment to its normal operation.
- E. If the equipment has been dropped, or the cabinet damaged.
- F. When the equipment exhibits a distinct change in performance — this indicates a need for service.

14. Replacement Parts

When replacement parts are required, be sure the service technician has used replacement parts specified by the manufacturer or that have the same characteristics as the original part. Unauthorized substitutions may result in fire, electric shock or other hazards.

15. Safety Check

Upon completion of any service or repairs to this equipment, ask the service technician to perform safety checks to determine that the equipment is in proper operating condition.

16. Field Installation

This installation should be made by a qualified service person and should conform to all local codes.

17. Correct Batteries

Warning: Risk of explosion if battery is replaced by an incorrect type. Dispose of used batteries according to the instructions.

18. Tmra

A manufacturer's maximum recommended ambient temperature (Tmra) for the equipment must be specified so that the customer and installer may determine a suitable maximum operating environment for the equipment.

19. Elevated Operating Ambient Temperature

If installed in a closed or multi-unit rack assembly, the operating ambient temperature of the rack environment may be greater than room ambient. Therefore, consideration should be given to installing the equipment in an environment compatible with the manufacturer's maximum rated ambient temperature (Tmra).

20. Reduced Air Flow

Installation of the equipment in the rack should be such that the amount of airflow required for safe operation of the equipment is not compromised.

21. Mechanical Loading

Mounting of the equipment in the rack should be such that a hazardous condition is not caused by uneven mechanical loading.

22. Circuit Overloading

Consideration should be given to connection of the equipment to supply circuit and the effect that overloading of circuits might have on over current protection and supply wiring. Appropriate consideration of equipment nameplate ratings should be used when addressing this concern.

23. Reliable Earthing (Grounding)

Reliable grounding of rack mounted equipment should be maintained. Particular attention should be given to supply connections other than direct connections to the branch circuit (e.g., use of power strips).

INDEX

1. SAFETY CAUTIONS	6
1.1 Power Source	6
1.2 Installation	6
1.3 Cleaning and Usage	7
2. OUTLINE	8
2.1 Functions	8
2.2 System Organization	9
3. DVR ORGANIZATION	10
3.1 Front Panel	10
3.2 Real Panel	13
3.2.1 DT Series	13
3.2.2 MT Series	14
3.3 Remote Controller	15
4. LIVE	16
4.1 Live Screen	16
4.1.1 Top Menu	17
4.1.2 Bottom Menu	17
4.1.3 CAMEO Menu	18
5. SETUP	21
5.1 GENERAL SETUP	21
5.1.1 GENERAL	22
5.1.2 ALARM OUT	24
5.1.3 DISK	24
5.1.4 MONITOR	30
5.1.5 ACCOUT	31
5.1.6 CONFIG	32
5.1.7 SHUTDOWN	33

INDEX

5.2 CAMERA SETUP	34
5.2.1 CAMERA	34
3.2.2 PTZ	35
5.2.3 SPOT	36
5.2.4 SEQUENCE	37
5.2.5 PRIVATE ZONE	38
5.3 EVENT SETUP	39
5.3.1 MOTION	39
5.3.2 ALARM IN	42
5.3.3 VIDEO LOSS	43
5.3.4 SYSTEM	44
5.3.5 DISPLAY	46
5.4 RECORD SETUP	47
5.4.1 RESOLUTION	47
5.4.2 SCHEDULE	48
5.4.3 RECORD	49
5.4.4 EVENT	50
5.4.5 AUDIO	50
5.4.6 MANUAL	51
5.5 ETHERNET SETUP	52
5.5.1 NETWORK	52
5.5.2 SERIAL	54
5.5.3 DDNS	55
5.5.4 E-MAIL	56
5.5.5 NET FRAME	57
5.6 SYSTEM SETUP	58
5.6.1 SYSTEM LOG	58
5.6.2 STATUS	59
5.6.3 VERSION	61
5.6.4 UPGRADE	61

INDEX

6. SEARCH	62
6.1 Search Screen	63
6.1.1 Search Menu	63
6.1.2 Calendar Search	64
6.1.3 Event Search	65
6.1.4 Overlapped List	66
6.1.5 Panorama Search	67
6.1.6 Section Repeat Search	67
6.1.7 Museum Search	68
7. BACKUP	71
7.1 Play with backup data	72
8. APPENDIX	73
8.1 Firmware Upgrade	73
8.2 Web Client	74
8.2.1 Web Viewer Functions	75
8.3 Trouble Shooting	76
8.4 Mobile Viewer	78

1. SAFETY CAUTIONS


- ※ Follow these instructions to keep the user safe and prevent property damage.
Read them carefully before the use of the product.
The responsibility falls on the user to install and use the product properly.

1.1 Power Source-related


- ① Insert the power plug fully and firmly into the power source.
– Unstable connection may cause fire.



- ② Do not use a damaged power cord, plug or loose outlet.
– It may cause electric shock or fire.



- ③ Do not plug several devices exceeding the rated capacity into a single outlet.
– Abnormal heat generation at the outlet may cause fire.



- ④ Do not bend nor pull the power cord. Do not place a heavy object on top of it.
– It may cause electric shock or fire.



- ⑤ When unplugging the power cord, do not pull it out by touching the cord area or do not touch it with a wet hand.
– It may cause electric shock or fire.



1.2 Installation-related

- ① Do not place candlelight or cigarette light on top of the product or do not install the product near heating devices.
– It may cause fire.



- ② Do not place the power cord near heating devices.
– The exterior of the cord may be peeled off, causing electric shock or fire.



- ③ Do not install the product in a place where a large amount of oil, smoke or moisture exists. Do not install the product in a vehicle or a place where water is splashed.
– It may cause electric shock or fire.



- ④ Do not place the product on top of an unstable cart, stand or table. Do not block the air ventilation with table cloth or curtain.
– Internal temperature rise may cause fire.



- ⑤ Do not install the product in a narrow place. Keep the product a certain distance away from the wall.
– Internal temperature rise may cause fire.



1.3 Cleaning and Usage-related

- ① Unplug the power plug during lightning, thunderstorm or when not in use for long periods of time.
- It may cause electric shock or fire.



- ② When taking the battery out from the remote control, keep them away from children to prevent from swallowing incidents.
Keep the battery away from babies.
- If a child swallowed the battery, immediately consult a doctor.



- ③ Do not place the container or base filled with water, liquids, chemicals, small piece of metal and heavy object on the product.
- If liquid flows into the product, it may cause electric shock or fire. A heavy object may drop from the top of the product, causing injury.



- ④ Do not use or store the product near combustible sprays and other flammable substances.
- It may cause explosion or fire.



- ⑤ If dust or water is present at the power plug's pin and contact area, wipe out the area.
- may cause electric shock or fire.



- ⑥ When cleaning the product, unplug the power cord and gently wipe using a soft cloth. Do not directly spray water on the product or do not use benzene, thinner or alcohol when cleaning.
- It may cause electric shock or fire.



- ⑦ When replacing the battery, be sure to check the correctness of the polarity (+,-).
- If the battery polarity is wrong, generation of abnormal heat or leakage of internal liquid may cause fire, injury or contamination in the surrounding area.



- ⑧ In case the product was dropped or the case was damaged, switch off the product and unplug the power cord. Have a technician repair the product.
- If the damaged product is used without repair, it may cause electric shock.



- ⑨ Do not repair or disassemble the product by yourself or do not connect other connection devices without the manufacturer's approval.
- If repair is required, contact the reseller. Failure to follow this instruction may cause electric shock or fire.




2. OUTLINE

2.1 Functions

This DVR provide Full HD Display and Playback.

- Based on Private Development ASIC Technology and Linux OS.
- Pentaplex Operation Performance (Live, Recording, Playback, Backup, Network)
- 16CH / 8CH / 4CH HD-SDI (SMPTE 292M) Video input.
- 1080P / 720P video compression.
- Various Recording mode. (Manual / Schedule / Event)
- Various Search functions. (Date/Hour search, Calendar search, Event Search)
- Various Playback functions. (Normal / Fast / Slow / Step / Reverse / Smart / Panorama / Repeat)
- Support E-SATA & SATA II
- Digital Zoom in Playback.
- Gigabit Network.
- Support 16channel Audio.
- Support Mouse control.
- E-mail function (Alarm, Motion detection, Video loss, HDD fail end etc)

2.2 System Organization




3. DVR ORGANIZATION

3.1 Front Panel Description

NOTE: Turn on the DVR after connecting the power cord, camera input and monitor completely

▪ HT-1641/1621/841



▪ HT-821 / 421



▪ HTS-400



※ STATUS LED

Recording LED

Recording LED is turned on when DVR is recording.

Network LED

Network LED is turned on when DVR is connected by network

※ Front Button

The front panel of DVR is similar as normal VCR or Multiplexer and the functions are also similar . Front buttons have various functions and are used for DVR initial setting and others. Please refer to the below explanation.

NUMBER buttons (0 ~ 9)

Displayed selected camera number to full screen.
And also these buttons are used to enter a password.

NOTE: If user want to use over than 10 channel, use the +10 button.

Ex) $10 + 1 = 11$, $10 + 6 = 16$

DISPLAY button

Display split screens 1, 4, 7, 9, 10, 13, 16.

REC button

Start recording when this button is pressed in live mode.

MENU button

Enter Setup menu. User need to Admin access permission.
Return to previous screen if this button is pressed again.

ESC button

Exit current screen or return to previous screen.

ROTATE button (Preset)

Display next channel if this button is pressed.
In PTZ mode, It is used Preset function button.

BACKUP button (Zoom)

Enter Backup menu. Return to previous screen if this button is pressed again.
In PTZ mode, it is used Zoom function button.

SEARCH button (Focus)

Enter Search menu. The password is required for search.
Return to previous screen if this button is pressed again.
In PTZ menu, it is used Focus function button.

PAUSE button (IRIS)

In Search mode, playback is paused by this button.
In PTZ mode, it is used IRIS function button.

Direction buttons (▲, ▼, ◀, ▶)

This buttons are used when move to other menu or change the position of the CAMEO screen.
In PTZ mode, it is used PAN/TILT function.

- ▲ : In Playback mode, it is Panorama search function button.
In PTZ mode, it is used to move the camera to up.
- ▼ : In Playback mode, it is Smart search function button.
In PTZ mode, it is used to move the camera to down.
- ◀ : In Playback mode, it is reverse play button and when paused screen,
user can see each frame if this button is pressed manually.
In PTZ mode, it is used to move the camera to left.
- ▶ : In Playback mode, it is forward play button and when paused screen,
use can see each frame if this button is pressed manually.
In PTZ mode, it is use to move to camera to right.

NOTE: For the Smart search, recording data should be recorded by the Event recording.

Otherwise, if user try to playback with Smart search, the screen is returned to live mode.

ENTER button

Execute the selected button or save the setup value.

FAST REVERSE PLAY button (PTZ)












Playback with fast reverse. Playback speed is changed if this button is pressed repeatedly. (◀, ◀◀, ◀◀◀, ◀◀◀◀, ◀◀◀◀◀). In PTZ mode, it is used to Zoom out function button.
In live mode, switch to PTZ mode by this button.

FAST FORWARD PLAY button (PLAY)

Playback with fast forward. Playback speed is changed if this button is pressed repeatedly. (▶, ▶▶, ▶▶▶, ▶▶▶▶, ▶▶▶▶▶). In PTZ mode, it is used to Zoom in function button.
In live mode, the last portion of recorded video is played.


3.2 Real Panel

▪ HT-1641/841




3.2 Real Panel


▪ HT-1621




▪ HT-821/421



▪ HTS-400



3.3 Remote Controller




※ How to set ID

- ① Before setup the ID, Enter to the GENERAL SETUP and set the ID first. (Default is 0)
- ② While pressing and holding the ID button, enter the unit address of the DVR by two-digit.
- ③ If the unit address is a single digit, enter two digit number by adding the number 0 as the first digit.
(Example – If the unit address is 1, the input value is 01.)

※ A single remote controller can change ID from 0 to 19 and independently control up to 20 DVRs.

4. LIVE

4.1 Live Screen



- Record Icon (Red)
When record in live screen.



- Video-loss Icon
When there is no video input.



- Time Icon
When record by designated time.



- Audio Icon
When sound is generated in live mode.



- Motion Icon
When motion is occurred.



- Freeze Icon
When live is paused.



- Sensor Icon
When sensor is occurred.



- Sequence Icon
When screen is rotated continuously.

4.1.1 Top Menu


In live screen, if ▲ button of the remote controller or front panel is pressed, or if the mouse cursor is placed over the end of the top area, the top menu is appeared.



Search Backup Status Setup Log-out

4.1.2 Bottom Menu


In Live screen, if ▼ button of the remote controller or front panel is pressed, or if the mouse cursor is placed over the end of the bottom area, the bottom menu is appeared.




1 4 7 9 10 13 16

4.1.3 CAMEO Menu

In live screen, if the ENTER button of the remote controller or front panel is pressed, a blue square cursor will be appeared. If the ENTER button is pressed again, the CAMERA menu will be appeared.



- **CAMEO CHANGE** : The live camera can be changed to the selected channel. If the camera number is selected at the pop-up menu shown below, the camera is changed to the selected channel.



- **PLAYBACK** : Playback on selected channel. (before 15~20 seconds)
- **FREEZE** : Live screen of the selected channel can be paused.
- **FREEZE ALL** : Live screen of the all channels can be paused.
- **SEQUENCE** : Live screen is rotated.

- **PTZ** : PTZ Camera should be installed otherwise the PTZ menu is not activated.

The following picture will be appeared when select PTZ menu and select [MENU] button.



- ※ **Using Mouse** : On the above menu, when click the right button of mouse, the control screen for Menu, Zoom, Focus and Iris will be appeared.



메뉴
Z+ / Z- : Zoom In / Zoom Out
F+ / F- : Focus In / Focus Out
I+ / I- : Iris In / Iris Out

- ※ **Using Remote Controller or Front Key** : The below Hot Key is available.

- Press the ENTER button on PTZ Camera channel.
- Press the ENTER button again then the CAMEO menu will be appeared.
- Select PTZ menu on the Live CAMEO menu.
- Press the ENTER button again, the above PTZ menu screen will be appeared.
- **Zoom Control** : In PTZ mode, press the Zoom (Back) button.
 Zoom in - Fast reverse play button / Zoom out - The fast forward play button.
- **Focus Control** : In PTZ mode, press the Focus (Search) button.
 (+) - Fast reverse play button / (-) – Fast forward play button.
- **Iris Control** : In PTZ mode, press the Iris (Pause) button.
 (+) – Fast reverse play button / (-) – Fast forward play button.



- **SPEED SETUP** : Set the PTZ camera speed. (1 to 8)

NOTE: If the mouse is used to move the PTZ camera, the movement speed depends on the position of the mouse. As the mouse pointer moves away from the center, speed becomes faster.

- **PRESET SETUP** :

Set the preset position. If the position setup is saved, PTZ camera will be directed to the set position by preset number.

- **PRESET TOUR** :

6 different preset list can be created. If the created preset lists are set to "ON", recording is made with preset tour.

- **PATTERN SETUP** :

Pattern can be created by movement, zoom, focus and iris. After pressing the BEGIN button, adjust the PTZ camera position or zoom and then press the END button. All directions (up, down, left and right), zoom and iris settings are recorded.

- **PATTERN TOUR** : PTZ camera moves according to the saved pattern.

- **AUTO FOCUS / POWER / LIGHT** :

Auto focus, power and light functions can be turned on/off on each category.

- **OSD MENU** : Turn on/off the OSD menu.

▪ **ZOOM X2** : Zoom in x2.

▪ **ZOOM X4** : Zoom in x4.

▪ **AUDIO ON** : Turn on/off Audio.

5. SETUP

In this category, there are General, Camera, Event, Schedule, Ethernet and System Information.

On the Top menu, select the [SETUP] menu.



After select the menu, the following Log-in window will be appeared.



LOGIN

ID		root			
PASSWORD		****			
0	1	2	3	4	←
5	6	7	8	9	

✓ ×

Enter the password by the key buttons and press the ENTER button.

(The default password : 1111)


5.1 GENERAL SETUP

In this category, there are General, Alarm, Disk, Monitor, Account, Configuration setup and Shutdown.

Select the [GENERAL] menu.



5.1.1 GENERAL




[SYSTEM]

- **LANGUAGE** : Select the language.
(English, Germany, French, Spanish, Japanese, Chinese, Italian, Russian, Dutch and Korean)
- **KEY TONE** : Turn on/off the buzzer sound of key.
- **UNIT ADDRESS** : Set the DVR ID.
This ID can be used when use multi DVR in same place by one remote controller.
- **BASE CAMERA NO.** : Set the beginning number of camera.
If set this value to 17, the camera number start with 17.
- **MENU TIMEOUT** : Keep the Menu screen for this value then escape from Menu.
- **PLAYBACK PROTECT** : Prohibit the playback of passed data.
(Select 0 to 99 days. If set 3 days, can not playback the data that elapsed 3 days.)
- **BACKUP CONFIRM** : Confirm the backup process.(Log-in process)
- **HDD OVERWRITE** : Select on/off to overwrite data on Hard disk.

NOTE: If set to [OFF], recording will be stopped automatically when disk is full.

5.1.1 GENERAL




[DATE / TIME]

- **DATE FROMAT** : Select the data format.
(YY/MM/DD) / (MM/DD/YY) / (DD/MM/YY)
- **TIMEZONE** : Select the timezone and DST.
The city which don't use DST is set to [OFF] automatically.
- **DATE DISPLAY** : Display date on live screen or not.
- **DATE / TIME** : Change date and time.
- **NTP** : Select the usage of NTP setting.
DVR time is synchronized with NTP server and get the standard time.
The default server is [pool.ntp.org] and User can input other server.


[Sync now] : Synchronize immediately.
[Auto Sync] : Synchronize every day automatically.
- **HOLIDAY** : Add or delete holiday.

5.1.2 ALARM OUT



- **SIGNAL** : Select on/off to use alarm by channel.
- **ALARM SET** : Check the alarm connection whether it works properly or not.
Press the [SET] button then alarm device will be operated.
- **ALARM CLEAR** : Press the [CLEAR] button then alarm device will not be operated.


5.1.3 DISK



※ **NOTE :**
*When install HDD first time,
 after install HDD, should
 format by the [INSTALL]
 button.*


[HDD] - When select the HDD under [TYPE], HDD information will be displayed.

[INSTALL] - Display initial HDD install and information.



[CHECK / USB]

- **EARLIEST RECORD** : Display the earliest recorded data information.
- **LATEST RECORD** : Display the latest recorded data information.
- **DISK CHECK** : Check the data from the earliest recorded to the latest recorded.
- **USB RESET** : Reset the USB connection.
- **USB FORMAT** : Format the connected USB.



[RAID] ※ This function for only DT series.

- **RAID SETUP** : Select the RAID level (RAID0, RAID1 and RAID5).
- **RAID** : Display RAID on/off status.
- **DISK STATUS** : Display disk status.
- **RAID STATUS** : Display RAID status.
- **RATE** : Display process rate.

!WARNING!

- ※ **By the RAID LEVEL, minimum 2 or 3 hard disk should be installed.**
- ※ **Hard disk should be used same model for RAID.**
- ※ **If hard disk brand or model is different, Disk error can be happened.**



When setup the RAID, above message will be appeared.


After select the “V” mark, DVR will be rebooted.

※ Rebooting for RAID, booting time is longer than normal. (About 5 minutes)

!WARNING

※ When RAID is built, all data of HDD will be deleted.

※ If data is saved on HDD, backup the data.




After build RAID, the type will be changed to [RAID] and recognize to 1 HDD.

Supported RAID level is 0, 1, 5.


※ RAID 0

- For building RAID Level 0, it will take about 5 minutes.
- Displayed with [GOOD], if the building is finished without any problem



※ RAID 1

- For building RAID Level 1, building time depends on the HDD capacity.
(In case of 1TB HDD, it will take 24~48 hours)
- Check the status on [RAID STATUS] and [RATE].




※ RAID 5 (Only support HT-1641/ HT-841)

- For building RAID Level 1, building time depends on the HDD capacity.
(In case of 1TB HDD, it will take 24~48 hours)
- Check the status on [RAID STATUS] and [RATE].


The screenshot shows the 'DISK SETUP' utility interface. It features a sidebar with menu items: GENERAL, ALARM OUT, DISK, MONITOR, ACCOUNT, CONFIG, and SHUTDOWN. The main area is divided into tabs: INSTALL, CHECK / USB, and RAID. The RAID tab is active, displaying 'RAID SETUP' as 'LEVEL 5'. Below this, a table shows the 'RAID' configuration for 'LEVEL 5' across ten HDDs. The 'DISK STATUS' table shows that HDD1, HDD2, and HDD3 are in 'BUILD' state, while HDD4, HDD5, HDD6, HDD7, HDD8, HDD9, and HDD10 are in 'NONE' state. The 'RAID STATUS' is 'BUILDING' and the 'RATE' is '44 % (INIT)'. At the bottom, there are two buttons: a checkmark (confirm) and an 'X' (cancel).

RAID		LEVEL 5				
DISK STATUS	HDD1	HDD2	HDD3	HDD4	HDD5	
	BUILD	BUILD	BUILD	NONE	NONE	
	HDD6	HDD7	HDD8	HDD9	HDD10	
	NONE	NONE	NONE	NONE	NONE	
RAID STATUS	BUILDING					
RATE	44 % (INIT)					

5.1.4 MONITOR



- **RESOLUTION** : Select the resolution for connected monitor.
If you select the [AUTO] option, HDMI monitor recognize the monitor resolution automatically.
- **VIDEO OUT** : Select main monitor. (MAIN-VGA / AUX-BNC Monitor)
(Fix the screen by connected monitor)
- **OSG OUT** : Select the monitor for menu scree to display.
- **BORDER COLOR** : Change the border color.
- **ALPHA BLENDING** : Set the transparency of menu.
(Set 1 to 20 and 20 is closer to the more transparent.)




[RESOLUTION selected screen]



[ALPHA BLENDING selected screen]

5.1.5 ACCOUNT



- ※ Add / delete any user and give permission freely.
- ※ When add new user, have to input new password.
When delete use, confirm again.

NOTE: (Default ADMIN password is 1111), Initial user name can be modified but can not delete.


CAUTION:

Default Admin account must not be deleted before add new user.

If delete default Admin user before add new Admin user, can not access on [SETUP] menu.

- ※ By the [PERM] menu, can give permission to each ID.


5.1.6 CONFIG



- **SLOT** : Select the slot to load or save on DVR memory.
 - ※ **DEFAULT** : Change factory default setting.
- **DATE** : Display the latest saved date.
- **LOAD** : Load the saved data.
- **SAVE** : Save the set data.
- **DEL** : Delete the saved data on Slot.
- **EXPORT** : Export the set data to USB or DVD.
- **IMPORT** : Import the set data to USB or DVD.




[DEFAULT selected screen]



[EXPORT selected screen]

5.1.7 SHUTDOWN



- **RESTART** : Restart the DVR.
- **SHUTDOWN** : Shutdown the DVR.

5.2 CAMERA SETUP

In this category, there are Camera, PTZ, Spot, Sequence and Private Zone setting.

Select the [CAMERA] Menu.



5.2.1 CAMERA

CAM	NAME+	INSTALL+	HIDDEN+
1	C01	ON	OFF
2	C02	ON	OFF
3	C03	ON	OFF
4	C04	ON	OFF
5	C05	ON	OFF

- **CAMERA LABEL** : Select the camera label of live screen.
(ALL / NUMBER / NAME / OFF)
- **NAME** : Change the camera name. (If select the camera name, the virtual keyboard will be appeared.)
- **INSTALL** : Select On/Off button to use camera.
- **HIDDEN** : Select On/Off button to hide camera on live view. (Record operate correctly.)


NOTE: If select [INSTALL] – [OFF], Camera name and number are not displayed.



[Virtual Keyboard]

If select the camera name, the virtual keyboard will be appeared. Max camera name should be less than 11 character.

5.2.2 PTZ




[PTZ]

- **PORT** : Select the Baud Rate for using PTZ camera.
- **ID** : Select the ID for using PTZ camera.
- **TYPE** : Show the PTZ protocol list.

NOTE : baud rate, data bit, parity, stop bit, ID and protocol depend on PTZ camera for using.

CAUTION : When connect the camera on the RS-485 port, refer to the manual of camera manufacture.

5.2.3 SPOT



CAMERA : Select the camera for display on spot monitor.


DEFAULT : Select the camera for display on spot monitor when sequence is off.

SEQUENCE : Select On/Off for sequence screen.

INTERVAL : Select the interval time to move next channel. The max value is 256 sec.

POPUP : Select On/Off for pop-up screen when event is occurred.

NOTE: Same channel image can not be displayed on each spot monitor.




[CAMERA selection screen]



[INTERVAL selection screen]

5.2.4 SEQUENCE




PAGE DWELL TIME : Select the dwell time to move next channel.

CAMEO DWELL TIME : Select the dwell time for CAMEO sequence.

NOTE: *CAMEO sequence means selected camera is rotated in select cameo of division screen.
Camera image which is shown on the other CAMEO of division screen is not included in CAMEO sequence.*




[DWELL-TIME selected screen]



[CAMERA SELECT screen]


5.2.5 PRIVATE ZONE



- **ZONE ENABLE** : Select On/Off to use. (LIVE mode/ SEARCH mode)
- **ZONE COLOR** : Select the color to hide.
- **ZONE** : Select the zone to hide.
(When select the ZONE button, the camera image will be appeared.)

NOTE : *Move the blue dot to a desired location and press the OK button.
Drag and move it to include the desired area and press the OK button.
As a result, the area is covered and hidden with the selected color*

TIP : *On the screen, if click the right button of mouse, a menu will be appeared.
Using this menu, a selected area can be delete or saved, or returned previous menu.*



[ZONE selected screen]



[Mouse right button selected screen]


5.3 EVENT SETUP

In this menu, there are Motion, Alarm in, Video Loss, System and Display setup.

Select the [EVENT] menu.



5.3.1 MOTION




[INPUT]

- **ACTIVE** : Select On/Off to activate motion.
- **LEVEL** : Select the sensitive for motion trigger. (Select 1 to 5 level)
- **AREA** : Select the motion area.

TIP: If select the ACTIVE+ / LEVEL+ / AREA+ menu, can change all settings at once.


▪ AREA SETUP




In the Area setup, the Red square is shown at the left top side of the screen. If select the OK button, the dot color will be changed to Green. A motion area can be selected by the direction buttons.

***NOTE : When the status is Red square, can move any direction to select.
When the status is Green color, can select motion area or cancel the set area.***

After set the motion area, if select the MENU button, the following screen will be appeared.




- **SELECT ALL** : Select all motion area.
- **CLEAR ALL** : Clear all motion area.
- **SAVE** : Save the changed setting.
- **CLOSE** : Close the pop-up screen.
- **EXIT** : Exit the motion area setup.




[ACTION]

- **RECORD** : Select the channel for record.
- **ALARM** : Select On/Off for alarm.
- **BUZZER** : Select On/Off for buzzer.
- **PRESET** : Set the preset number.
 (When motion is triggered, the PTZ camera move to the set preset number position)
- **E-MAIL** : Select On/Off for e-mail notification.

TIP: If select to the [DEFAULT], only record the channel which is occurred event.



5.3.2 ALARM IN




TIP:

If select the ACTIVE+ / TYPE+ menu, can change all settings at once.

[INPUT]

- **ACTIVE** : Select On/Off to activate alarm.
- **NAME** : Type any name.
- **TYPE** : Select the alarm type. (NO : Normal Open / NC : Normal Close)



[ACTION]

- **RECORD** : Select the channel for record.
- **ALARM** : Select On/Off for alarm.
- **BUZZER** : Select On/Off for buzzer.
- **PRESET** : Set the preset number.
(When motion is triggered, the PTZ camera move to the set preset number position)
- **E-MAIL** : Select On/Off for e-mail notification.


5.3.3 VIDEO LOSS



TIP:
*If select the ACTIVE+ menu,
 can change all setting at once.*

[INPUT]

- **ACTIVE** : Select On/Off to activate.



[ACTION]

- **RECORD** : Select On/Off for record.
- **ALARM** : Select On/Off for alarm.
- **BUZZER** : Select On/Off for buzzer.
- **PRESET** : Set the preset number.
 (When motion is triggered, the PTZ camera move to the set preset number position)
- **E-MAIL** : Select On/Off for e-mail notification.


5.3.4 SYSTEM

MOTION	WARNING	DISK	E-MAIL
ALARM IN	CHECK INTERVAL	1 HOUR	
VIDEO LOSS	DISK WARNING	POPUP	
SYSTEM	ALARM WARNING	OFF	
DISPLAY	THRESHOLD	54	C
	CURRENT TEMP	38 C	
	FAN SPEED WARNING	POPUP	
	THRESHOLD	1500 RPM	
	CURRENT SPEED	6120 RPM	

✓ ✕


[WARNING]

- **CHECK INTERVAL** : Select the check interval time. (Select 1 hour to 24 hour)
- **DISK WARNING** : Select the option for smart warning. (POPUP + BUZZER / POPUP / OFF)
- **ALARM WARNING** : Select the alarm out channel for Alarm warning.
- **THRESHOLD** : Select the warning temperature. (C: 0 to 100 / F : 32 to 212)
- **CURRENT TEMP** : Display current temperature.
- **FAN SPEED WARNING** : Select the option for smart warning. (POPUP + BUZZER / POPUP / OFF).
- **THRESHOLD** : Select the RPM speed.
- **CURRENT SPEED** : Display current RPM.



[DISK]

- **DISK FULL WARNING** : Select On/Off to disk full warning.
- **USED SPACE** : Select the used space for warning.
- **ALARM** : Select the alarm out channel for the USED SPCE warning.
- **BUZZER** : Select On/Off for the USED SPCE warning
- **MESSAGE** : Select On/Off for message.



[MAIL] – Select option for e-mail notification and set On/Off.

- **POWER / MENU / LOGIN FAIL / DISK FULL / LOG IN / SMART**

5.3.5 DISPLAY

CAMERA	DISPLAY+
1	2 SEC
2	2 SEC
3	2 SEC
4	2 SEC
5	2 SEC

EVENT ICON	ON
EVENT POPUP	OFF

- **DISPLAY** : Select display time by second. (Select 0 to 100)
- **EVENT ICON** : Select On/Off to display event icon.
- **EVENT POPUP** : Select On/Off to pop-up.


5.4 RECORD SETUP

In this menu, there are Resolution, Schedule, Record, Audio, Manual, Filter setup.

Select the [RECORD] menu.



5.4.1 SCHEDULE



- **SETUP MODE** : Select the record schedule. (TYPICAL / CUSTOM)

[TYPICAL]


- **DAY TIME** : Select the day time. (The night time is changed automatically according to the day time zone)
- **WEEKEND** : Set the weekend zone.

[CUSTOM]

- Set 3 different recording setup by day and time. (REC0, REC1, REC2)

This is related with [RECORD] menu so [CUSTOM] mode should be matched with [RECORD] menu.

TIP : For REC0, REC1, REC2 recording, change the setting [SETUP MODE] to [TYPICAL] and enter to the [RECORD] menu then change the setting.



[CUSTOM selected screen]

5.4.2 RECORD



[DAY] / [NIGHT] / [WEEKEND]

- **TIME** : Set the recording frame and resolution by channel.
- **EVENT** : Set the event recording. (Frame / Resolution / Post recording time [5 to 100 second])


TIP : The frame can be set by the direction button in setup screen.

If set to [CUSTOM] in [SCHEDULE] menu, the DAY / NIGHT / WEEKEND menu will be changed to REC0/ REC1 / REC2. Also set the frame and resolution.



[RECORD] screen after select [CUSTOM] menu


5.4.3 EVENT



- **EVENT** : Select the Pre recording time and Post recording time.


TIP: If select the RECORD+ menu, can change all setting at once.

5.4.4 AUDIO



- **AUDIO** : Select On/Off for audio recording by each channel.

5.4.5 MANUAL



Manual Recording is same as Panic recording.

This function can be worked by the [REC] button on Remote controller or Front panel.

- **SPEED** : Select the recording frame by each channel.
- **Quality** : Select the resolution by each channel.
- **AUDIO** : Select On/Off for audio recording by each channel.

5.5 ETHERNET SETUP

In this menu, there are Network, Serial, DDNS, E-mail setup.

Select the [ETHERNET] menu.



5.5.1 NETWORK

NETWORK	ETHERNET	CLIENT
SERIAL	DYNAMIC IP ON	
DDNS	HOST NAME dvr	
E-MAIL	IP ADDRESS 192.168.1.21	
NET FRAME	SUBNET MASK 255.255.255.0	
	GATEWAY 192.168.1.1	
	DNS SERVER 192.168.1.1	
	CHECK INTERNET	START


[ETHERNET]

- **DYNAMIC IP** : Select On/Off for dynamic IP.

If Dynamic IP is OFF, DVR get IP address from router automatically.

- **HOST NAME** : Type any Host name.
- **IP ADDRESS** : Type IP address. (Available when DYNAMIC IP is OFF)
- **SUBNET MASK** : Type Subnet mask. (Available when DYNAMIC IP is OFF)
- **GATEWAY** : Type Gateway. (Available when DYNAMIC IP is OFF)
- **DNS SERVER** : Type DNS server. (Available when DYNAMIC IP is OFF)
- **CHECK INTERNET** : Check internet status for use.

5.5.1 NETWORK



The screenshot shows a 'NETWORK SETUP' window with a 'CLIENT' tab selected. The interface includes a sidebar with 'NETWORK' options and a main configuration area with two columns: 'ETHERNET' and 'CLIENT'. The 'CLIENT' column contains several rows for configuration, including 'CLIENT ACCESS', 'BEGIN ADDRESS', 'END ADDRESS', 'SMS PORT (TCP)', 'WEB PORT (TCP)', 'REMOTE RESTART', and 'REMOTE CONFIG'. At the bottom, there are 'OK' and 'Cancel' buttons.

NETWORK	ETHERNET	CLIENT
SERIAL		CLIENT ACCESS: ALL
DDNS		BEGIN ADDRESS: 0.0.0.0 END ADDRESS: 0.0.0.0
E-MAIL		BEGIN ADDRESS: 0.0.0.0 END ADDRESS: 0.0.0.0
NET FRAME		SMS PORT (TCP): 7000
		WEB PORT (TCP): ON 80
		REMOTE RESTART: OFF
		REMOTE CONFIG: ON

[CLIENT]

- **CLIENT ACCESS** : Select client access options. (ALL / RANGE)
- **BEGIN ADDRESS / END ADDRESS** (When select RANGE option, type the IP address to accept)
: Input the acceptable IP address.
- **SMS PORT (TCP)** : Select SMS port.
- **WEB PORT (TCP)** : Select Web port.
- **REMOTE RESTART** : Select On/Off to restart DVR at remote.
- **REMOTE CONFIG** : Select On/Off to change configuration.

5.5.2 SERIAL

SERIAL SETUP

NETWORK		
SERIAL	RS-232 INPUT SETUP	
	SERIAL TYPE	NONE
DDNS	MODEL	NONE
E-MAIL	PORT	9600-8N1
NET FRAME	RS-485 INPUT SETUP	
	SERIAL TYPE	NONE
	MODEL	NONE
	PORT	9600-8N1

✓ ✕

[RS-232 INPUT SETUP]

- **SERIAL TYPE** : Select external device.
- **MODEL** : Select the protocol to use.
- **PORT** : Select the Baud Rate / DATA bit / Parity / Stop Bit.

[RS-485 INPUT SETUP]

- **SERIAL TYPE** : Select external device.
- **MODEL** : Select the protocol to use.
- **PORT** : Select the Baud Rate / DATA bit / Parity / Stop Bit.

5.5.3 DDNS

DDNS SETUP

NETWORK		
SERIAL		
DDNS	DDNS SERVER	ddnsdvr.com
E-MAIL	HOST NAME	test.ddnsdvr.com
NET FRAME	USER NAME	test
	PASSWORD	****
	ROUTER IP	OFF
	STATUS	UNCHECKED CHECK

✓ ✕


- **DDNS SERVER** : Select DDNS server. (Ddnsdvr.com / Dyndns.com / ChangeIP.com)
- **HOST NAME** : Input the host name from the registered on DDNS server.
- **USER NAME** : Input the user name from the registered on DDNS server.
- **PASSWORD** : Input the password from the registered on DDNS server.
- **ROUTER IP** : Select On/Off for sending IP information to the DDNS server.
If use any router, this setting should be [ON].
- **STATUS** : Check the connection status.

NOTE : For using DDNS server, firstly connect the DDNS server and register Host name, User name password then input those information on above menu.

Example for DDNSDVR

- In web browser, visit www.ddnsdvr.com
- Click the [New Account] menu on the left menu.
- Input the User / Email / Password that user wants.
- Click the [Log In] menu on the left menu and log in by the created new account.
- Click the [New hostnames] and make new host name.
→ In DVR menu, should be inputted full host name such as [\[peterlim-astel.ddnsdvr.com\]](http://peterlim-astel.ddnsdvr.com)
- Click the [List hostnames] and check the created hostname.

5.5.4 E-MAIL




E-MAIL SETUP

<p>NETWORK</p> <p>SERIAL</p> <p>DDNS</p> <p>E-MAIL</p> <p>NET FRAME</p>	ADDRESS		SERVER	
	SEND MAIL	SCHEDULE	FROM	TO
	OFF	ON	00:00:00	23:59:59
	NO.	E-MAIL ADDRESS		
	1			
	2			
	3			
4				
5				
6				

✓ ✕

[ADDRESS]

- **SEND E-MAIL** : Select On/Off for use.
- **SCHEDULE** : Set the usage time. (From : Start time / To : End time)
- **E-MAIL ADDRESS** : Input the E-mail address to receive.



E-MAIL SETUP


<p>NETWORK</p> <p>SERIAL</p> <p>DDNS</p> <p>E-MAIL</p> <p>NET FRAME</p>	ADDRESS		SERVER	
	MAIL SERVER		SMTP SERVER	
	E-MAIL		email@ddnsdvr.com	
	PASSWORD		****	
	SMTP SERVER		ddnsdvr.com	
	SMTP PORT		25	
	MAIL TEST		SEND	

✓ ✕

[SERVER]

- **MAIL SERVER** : Select the mail server. (SMTP server / DVR System)
- **E-MAIL** : Input the user e-mail address.
- **PASSWORD** : Input the Login password.
- **SMTP SERVER** : Input the server address.
- **SMTP PORT** : Input the server port.
- **MAIL TEST** : Send test mail.

5.5.5 NET FRAME



- **FPS** : Select the frame for the network transmission.
- **QUALITY** : Select the image quality for the network transmission.

5.6 SYSTEM SETUP

In this menu, there are System Log, Status, Version.

Select the [SYSTEM] menu.




5.6.1 SYSTEM LOG

NO.	DATE	SYSTEM LOG
0108	04/19 01:26:24	Schedule Changed
0107	04/19 01:26:15	Schedule Changed
0106	04/19 01:23:44	S.M.A.R.T. Error in HDD1
0105	04/19 01:23:43	HDD-1 SMART CRITICAL Realloc
0104	04/19 01:18:30	S.M.A.R.T. Error in HDD1
0103	04/19 01:18:29	HDD-1 SMART CRITICAL Realloc
0102	04/19 01:13:16	Login Success(ID:root)


- Check the system log by the left, right direction button.

5.6.2 STATUS




[DISK]

- Display HDD Status.
- **HDD INFORMATION** : Display the HDD status.
 - : DVR check the HDD bad sector automatically and if there is bad sector, skip the bad sector then record continuously.



5.6.2 STATUS




The screenshot shows the STATUS window with the RECORD tab selected. The window has a sidebar on the left with 'SYSTEM LOG', 'STATUS', and 'VERSION' options. The main area has sub-tabs for 'DISK', 'RECORD', and 'AUDIO'. Under 'RECORD', there are 'SCHEDULE' and 'REC 1' sub-sections. A table displays the following data:

CAM	RESOLUTION	TIME	EVENT
1	STD(CIF)	15, HIGH	15, HIGH
2	STD(CIF)	15, HIGH	15, HIGH
3	STD(CIF)	15, HIGH	15, HIGH
4	STD(CIF)	15, HIGH	15, HIGH
5	STD(CIF)	15, HIGH	15, HIGH
6	STD(CIF)	15, HIGH	15, HIGH
7	STD(CIF)	15, HIGH	15, HIGH

A close button (X) is located at the bottom right of the window.

[RECORD]

- Display RECORD Status.



The screenshot shows the STATUS window with the AUDIO tab selected. The window has a sidebar on the left with 'SYSTEM LOG', 'STATUS', and 'VERSION' options. The main area has sub-tabs for 'DISK', 'RECORD', and 'AUDIO'. Under 'AUDIO', there are 'CAMERA' and 'RECORD' sub-sections. A table displays the following data:


CAMERA	RECORD
1	OFF
2	OFF
3	OFF
4	OFF
5	OFF
6	OFF
7	OFF

A close button (X) is located at the bottom right of the window.

[AUDIO]

- Display AUDIO Status.


5.6.3 VERSION



SYSTEM LOG		
STATUS	DVR PROGRAM	0.00.00.01
VERSION	PRODUCT. DATE	Apr 19 2013, 10:52
	VIDEO CODEC	101112.0
	VIDEO	VIDEO 16CH CIF-480FPS
	AUDIO	AUDIO 4CH
	VIDEO FORMAT	NTSC
	MAC ADDRESS	00:19:19:02:43:91

- Display DVR version and information.

5.6.4 UPGRADE



SYSTEM LOG		
STATUS	TYPE	MEDIA
VERSION	DEVICE	NONE
UPGRADE	FILE NAME	dvr_upgrade_*
	CONFIRM	ON
	UPGRADE	START

- **TYPE** : Select the upgrade type. (FTP or Media)
- **DEVICE** : Select the device which have upgrade firmware file. (DVD / USB)
- **CONFIRM** : Select On/Off for upgrade confirm message.
- **UPGRADE** : Start upgrade.

6. SEARCH

On the Top menu, select the [SEARCH] menu.



After select the menu, the following Log-in window will be appeared.




Enter the password by the key buttons and press the ENTER button.

(The default password : 1111)




- **QUICK SEARCH** : Search by date, hour, minutes in detail.
- **CALENDAR** : Search by date and time with Calendar.
- **EVENT SERARCH** : Search by event
- **OVERLAPPED LIST** : Search the overlapped data by changing time
- **MUSEUM SEARCH** : Search by the selected area.
- **GO TO FIRST** : Search with initial saved data.
- **GO TO LAST** : Search with the latest saved data.

6.1 Search Screen Configuration




6.1.1 Search Menu

When mouse cursor is placed over on the bottom side, the Search menu is appeared.




※ As in the live screen, the top menu can be used in the search screen.

6.1.2 CALENDAR SEARCH



- a. Select the data by the direction button.
- Recorded data is displayed the orange color.



- b. Select the time by the direction button.
- After select hour, minutes will be appeared.

NOTE: The time graph color is different by the recording mode.

Continuous Recording = Blue, Audio Recording = Light Blue, Event Recording = Red.

6.1.3 EVENT SEARCH

EVENT SEARCH

EARLIEST RECORD	01/11/2013 19:30:20
LATEST RECORD	01/15/2013 16:40:13
DATE	01/11/2013
MOTION	ON
ALARM IN	ON
VIDEO LOSS	ON
SELECT CAMERA	ON

VIEW SEARCH LOG

X

- **DATA** : Select Date to search.
- **MOTION** : Select On/Off event for search.
- **ALARM IN** : Select On/Off event for search.
- **VIDEO LOSS** : Select On/Off event for search.
- **SELECT CAMERA** : Select the camera for search.
- **VIEW SEARCH LOG** : Display selected event log.

EVENT SEARCH RESULT

NO.	TIME	DST	CAMERA	EVENT
52	01/11/2013 20:10:00		1	MOTION
51	01/11/2013 20:09:12		1	MOTION
50	01/11/2013 20:08:15		2	VIDEO LOSS
49	01/11/2013 20:07:38		1	MOTION
48	01/11/2013 20:07:30		2	VIDEO LOSS
47	01/11/2013 20:07:30		1	MOTION
46	01/11/2013 20:07:20		2	VIDEO LOSS
45	01/11/2013 20:07:20		1	MOTION
44	01/11/2013 20:07:13		2	VIDEO LOSS


◀ 0 - 20 HOUR ▶

PREV NEXT GOTO


✓ X

- **HOURL** : Select time period to see.
- **PREV** : Display previous page.
- **NEXT** : Display next page.
- **GOTO** : Display the image by selected event.

6.1.4 OVERLAPPED LIST




- If user change the time or applied DST (Daylight Saving Time), there will be overlapped data.



- After select the list, if select the [PLAY] button, can search [QUICK SEARCH] or [EVENT SEARCH].

6.1.5 PANORAMA SEARCH

- During normal search, press the [PANORAMA] button.
- By mouse, click the right mouse button and click the [PANORAMA] Search.
- Playback with frame by frame.



6.1.6 SECTION REPEAT SEARCH

- During normal search, press the [LOCK] button or Click the below red circle button by mouse. When press one time, the start position is set, press one more time, the end position is set.




- In search screen, display the following mark.



6.1.7 MUSEUM SEARCH

- Select [MUSEUM SEARCH] menu by cameo function or playback bottom menu.



- Select the Museum search area.



6.1.7 MUSEUM SEARCH

- Select the Start time and End time to search then select SEARCH button.

MUSEUM SEARCH MENU (CAM1)


START TIME	04/18/2013	09:00:16
END TIME	04/18/2013	10:00:16
CAMERA	1	
AREA	SET	

SEARCH CLOSE

EXIT



- By playback bottom menu, displayed event list.



PREVIEW LIST (MUSEUM)

NO.	TIME
1	01/14/2013 18:25:15
2	01/14/2013 18:25:25
3	01/14/2013 18:26:19
4	01/14/2013 18:26:29
5	01/14/2013 18:26:39
6	01/14/2013 18:26:51
7	01/14/2013 18:27:46
8	01/14/2013 18:28:07
9	01/14/2013 18:28:17
10	01/14/2013 18:28:27

PREVIEW

- Select the event then playback with selected event.

※ Button Explanation in Search mode

- Remote Controller or Front button

Button	Explanation
SEARCH	Display the [SEARCH] menu.
ESC	Cancel the Search mode or return to the live screen.
ENTER	Select the CAMEO menu.
FAST REVERSE	When reverse play, up and down play speed.
FAST FORWARD	When forward play, up and down play speed.
PAUSE	Pause the playback.
FORWARD PLAY	Playback the data.
REVEERSE PLAY	Reverse Play the data.
DISPLAY	Display division screen. (1,4,9,16)

7. BACKUP

On the Top menu, select the [BACKUP] menu.



After select the menu, the following Log-in window will be appeared.

LOGIN

ID		root			
PASSWORD		****			
0	1	2	3	4	←
5	6	7	8	9	

✓ ✕

Enter the password by the key buttons and press the ENTER button.

(The default password : 1111)

MANUAL BACKUP


TARGET	NONE	NONE
FROM	01/11/2013	19:30:20
TO	01/14/2013	19:24:39
BACKUP TITLE	backup	
SELECT CAMERA	ON	
EARLIEST RECORD	01/11/2013 19:30:20	
LATEST RECORD	01/14/2013 19:24:39	
REQUIRE SPACE	ESTIMATE	0.00MB

WRITE

✕

- **TARGET** : Select the device to backup. (USB / DVD)
- **FROM** : Select the start date and time.
- **TO** : Select the end date and time.
- **BACKUP TITLE** : Type any title.
- **SELECT CAMERA** : Select the camera for backup
- **EARLIEST RECORD** : Display the earliest record.
- **LATEST RECORD** : Display the earliest record.
- **REQUIRE SPACE** : Display the data capacity for selected data.
- **WRITE** : Start the backup.


7.1 Play with backup data




- After backup, the DVR Player is copied with data.
- Backup data only can be played on DVR Player at PC.
- Can export to JPEG still shot.

8. APPENDIX


8.1 Firmware Upgrade



- ① Copy the firmware on USB and connect on the USB port.
- ② For upgrade, restart the DVR.




- ③ After restart, when upgrade window is appeared, select the START button. √



- ⑤ After upgrade, remove the USB and select OK button. Then DVR is restarted. √

※ If select OK button without removing USB, DVR upgrade is started again after restart.




- ⑥ After restart DVR, can check that upgrade is finished.

8. APPENDIX


8.2 Web Client

※ How to connect

For using web connection through internet, 7000 and 80 ports should be set as port forwarding at the Router.




1. To connect Web viewer, the [Ethernet] setup on DVR is required firstly.



2. Input the IP address or Domain name of DVR


- <http://210.58.xx.xx>
- <http://test.ddnsdvr.com>
- In case of other Web port, input the address as <http://test.ddnsdvr.com:XXXX> ('XXXX' is assigned web port number)



3. User Have to allow download ActiveX

* In case of Windows not allow to download the ActiveX, Go to the Security Tab on IE and check all ActiveX to Enable.

4. Install the ActiveX



5. Input ID & Password then click the Connect button.

8.2.1 Web viewer Functions

The screenshot shows the 'Web Viewer v2.5' interface. It features a 2x2 grid of camera feeds: '1 C01 A' (hallway), '2 C02 A' (locker hallway), '3 C03' (restaurant), and '4 U:' (outdoor pool). The control panel on the right includes a clock (11:29:06), a 'Division screen' button, a 'Control' section with four numbered buttons (1-4), brightness and contrast sliders, a login section with 'USER ID' (remote) and 'Password' fields, and 'Connect' and 'Disconnect' buttons.

Labels on the right side of the interface:

- Division screen
- 1
- 2
- 3
- 4

Labels at the bottom of the interface:

- Connect
- Disconnect

Detailed views of the control panel buttons and their functions:

- 1** Control: Includes buttons for Home, PTZ, Alarm, and Play/Pause. Below are sliders for Brightness control and Contrast control.
- 2** PTZ: Includes buttons for Home, PTZ, Alarm, and Play/Pause. Below are directional arrows and buttons for Zoom In (+) and Zoom Out (-).
- 3** ALARM: Includes buttons for Home, PTZ, Alarm, and Play/Pause. Below are four buttons with alarm bell icons.
- 4** SEARCH: Includes buttons for Home, PTZ, Alarm, and Play/Pause. Below are playback controls (stop, play, pause, next, previous) and buttons for 'open' and 'exit'.

8. APPENDIX

8.3 Trouble Shooting


SYMPTOM	MEASURES
No Power	If the power LED is not lighted, check the below items. <ul style="list-style-type: none">- Check the power plug and outlet. (Refer to the [Cautions for safety])- Connect the power cord to the power connector of DVR properly.
No camera image	<ul style="list-style-type: none">- Connect the camera cable to the DVR port properly.- Check the connected monitor cable with DVR. (Refer to the [Rear Panel Configuration])- Check the camera power and lens setting.- As this may be caused by a temporary error, restart DVR.- As camera setting may be wrong, initialize the camera and DVR. <p>※ How to initialize DVR</p> <p>1. Main Menu > Configuration > Default Load > O.K > O.K</p> <p>!! Caution: After DVR initialization, DVR setting is returned factory default. Need to backup the configuration before initialize DVR.</p>
Not work mouse	<ul style="list-style-type: none">- USB mouse should be supported PS/2. Check the PS/2 support.- Mouse should be connected on port (B) properly. (Refer to the [Front Panel Configuration])- Reset the USB Mouse. (Set on [System Manager])
Not record on DVR	If the recording LED does not flicker, check the below items. <ul style="list-style-type: none">- HDD should have enough space otherwise could not be recorded.- Delete data in HDD or change the [HDD OVERWRITE] setting to [ON]. (Refer to the [GENEL Setup] – [HDD OVERWRITE])- Replace the HDD because the HDD may be failed.- Check the recording setup.
Not connected Network	If the network LED does not flicker, check the below items. <ul style="list-style-type: none">- Check the connected hub or router.- Check the network cable and connection.- Check the network setup.

<p>Not work remote controller</p>	<ul style="list-style-type: none"> - Check the battery polarity. - Check the remote controller ID. (Refer to the [Remote Controller Configuration]) - Focus on the remote controller to the IR sensor. - Use the remote controller within 7 meters from DVR. - Change the battery.
<p>No sound in live view</p>	<ul style="list-style-type: none"> - Check the mike and audio cable with DVR port. (Refer to the [Real Panel Configuration]) - Check the speaker power which is connected on Audio port. - Turn on the Audio in the CAMEO menu. (Select the channel which is connected Audio and turn on. ※ CAMEO menu will be appear when click the right button of mouse.)
<p>No sound in search</p>	<ul style="list-style-type: none"> - Set to [Audio] – [ON]. (If set to [OFF], sound is not heard during search.) - Although the record icon is lighted, if there is no audio input, sound is not heard. ※ Audio record can be changed [Main Menu] > [Record Setup].
<p>Not work smart search</p>	<ul style="list-style-type: none"> - For smart search, event record should be set. - If event record is not set, when select the smart search, return to the live screen from search mode.


8. APPENDIX

8.4 Mobile Viewer (Apple & Android)

- Download the [mpocketdvr] on App store. (Free software)
- Download the [pocketdvr] on Android market. (Free software)
- How to use two apps are the same.




- Execute the [mpocketdvr or pocketdvr] then appears the below screen. Press the [+] button and move to next step.






- Enter the DVR information for connection.




- After enter the DVR information, press the  button.

- On the DVR list, press the below red circle area then connections is started.




- ADD : Press the  button for other DVR.
After enter DVR information, press the  button.

- EDIT : Press the  button and modify the DVR information.
(Delete or modify)

- Support 1,2,8,16 split screen.
- By the screen touch, change 1 screen or multi screen.
- Horizontal view, Vertical view are supported.



- **Done** : Exit application.
- **Search** : Playback by date / time.
After select date and time, press the **Done** button for playback.
- **Live** : Return to live mode.



- Explanation of each button.



Image capture

: In 1 screen mode, save JPEG image by this button.



Pause

: In live view, image is paused by this button.



Paused Icon

: Press this button again, Pause is stopped by this button.



Screen Split

: Change to 2,8, 16 split screen by this button. For 1 screen view, double touch on the channel.



PTZ

: Control PTZ camera by this button.
Camera position is changed by the direction mark.

